Mikas Middle East **FZE**

Office No: 139/A, Building -Q1-04 **Sharjah Airport International Freezone** PO Box: 61397, Sharjah **United Arab Emirates.**

mikas.ae

ALTERNATOR DATA

Machinery for Industrial Kinetics, Access, and Services

250 KVA 3 PHASE 50H



GENERATING SET MODEL UPS P 250		
Output Ratings 380-415 V, 3 ph, 50 Hz, 1500 rpm	Prime	Standby
, , , , , , , , , , , , , , , , , , , ,	250 KVA	256 KVA
	200 KW	205 KW
380-415 V, 3 ph, 60 Hz, 1800 rpm	262 KVA	275 KVA
	210 KW	220 KW

ENGINE/ TECHNICAL DATA

Engine Make

Ratings at 0.8 Power Factor

PERKINS

g	
Engine Model	1506A-E88TAG3
Governing Type	Electronic
Number of Cylinders	6
Cylinder Arrangement	Vertical in line
Bore and Stroke mm	112 X 149
Displacement/ Cubic Capacity litres	8.8
Induction System	Turbocharged aftercooled
Cycle	4 stroke
Combustion System	Direct Injection
Compression Ratio	16.1:1
Frequency and Engine Speed	50Hz & 1500rpm 60Hz & 1800rpm

Gross Engine Power kW(hp)	222(298)	212(284.6)
Fuel Consumption @50% load L/hr	29	29
@75% load L/hr	42	42
@100% load L/hr	56	56
Total Lubrication System Capacity litres	41	41
Total Coolant Capacity (inc. radiator) litres	25	25

Exhaust Temperature: °C





275 KVA 60Hz **3 PHASE**

Make	UPS/ Leroy Somer	
Model	UPS274G/ (TAL)046E	
No. of Bearings	1	
Insulation class	Н	
Wires	6/12	
Ingress Protecti	11 23	
Excitation Syste	m Shunt	
Winding Pitch	2/3	

Overspeed	2250 mn-1
Voltage Regulation (Subady)	±1%

CONTROL PANEL

Make	DeepSea
Model	7000 Series

The DSE 7000 series is an Auto Start Control Module for single genset applications. It includes a backlit LCD display which clearly shows the status of the engine all the times. This module can either be programmed using the front panel or by using the DSE configuration suite PC software. **Metering and Alarm Indications:**

- Underspeed, Overspeed Generator volts (L-L-L-N)
- Generator current
- Engine oil pressure
- Engine coolant temperature
 - Hours run counter Battery volts
 - Fail to start/stop
 - Emergency stop
 - Failed to reach loading voltage/frequency
 - Charge fail
 - Low DC Voltage
 - CAN diagnostics and CAN fail/error



STANDARD SPECIFICATIONS

250 KVA 3 PHASE 50H

1. ENGINE

Perkins four stroke heavy duty high performance industrial type 7.1 INSULATION SYSTEM diesel engine.

2. ENGINE FILTRATION SYSTEM

- Cartridge type dry air filter.
- Two cartridge type fuel filter.
- Full flow lube oil filter
- All filters have replaceable elements.

3. COOLING RADIATOR

Radiator and cooling fan, complete with safety guards designed to cool the engine at high ambient temperatures (consult your dealer for de-ration factors)

4. EXHAUST SYSTEM

31..3 (m3/min) Exhaust gas flow Maximum allowable back pressure 18.0 (kPa)

5. CIRCUIT BREAKER TYPE

3 pole MCCB. (4 pole is optional)

6. FUEL SYSTEM

The baseframe design is incorporated with an integral fuel tank with a capacity of approx.. 8 hours running at Full load. The tank is supplied complete with fill cap breather, fuel feed and return lines to the Engine and the drain plug.

7. ALTERNATOR

- The insulation system is Class H.
- · All windings are impregnated in either a triple dip thermoset-Ting liquid, oil and acid resisting polyester varnish or vacuum pressure impregnated with a special polvester resin.
- · Heavy coat of antitracking varnish additional protection Against moisture or condensation

7.2 AUTOMATIC VOLTAGE REGULATOR (AVR)

The fully sealed Automatic Voltage Regulator maintains

The Voltage Regulation at ±1%. Nominal adjustment by means of a trim pot incorporated on the AVR.

8. MOUNTING ARRANGEMENT

8.1 COUPLING The Engine and Alternator are directly coupled by means of an SAE flange. The Engine flywheel is flexibly coupled to the Alternator rotor, 8.2 ANTI-VIBRATION MOUNTING PADS

Magneti-Vibration pads are affixed between Engine/Alternator feet and the Baseframe thus ensuring complete vibration isolation of the rotating assembly. 8.3 SAFETY GUARDS

The Fan & Fan Drive along with the battery Charging Alternator are Safety Guard protected for personnel protection

60Hz

275 KVA

3 PHASE

9. FACTORY TEST

- The Generating set is load tested before
- dispatch All protective devise control functions and site load conditions are simulated. The generator and its systems are checked before dispatch

10. EQUIPMENT FINISHING

All mild steel components are fully degreased and painted wit powder coated paint to ensure maximum scuff resistance and

Operation & Maintenance manual, Circuit wiring diagrams and Commissioning/ Fault Finding instruction leaflets are accompanied with the Generator.

12. QUALITY STANDARDS

The equipment meets the following standards, BS4999, BS5000, BS5514 IEC 60034, VDE0530, NEMA MG 1.22 and ISO 8528.

13. WARRANTY


All of the Generating sets are covered under a warranty policy For a period of 12 months or 1000 working hours. Warranty of the equipment is in line with manufacturers warranty terms & conditions. (check warranty statement for more details, as it may vary for different countries.)


In line with the continuous product development, we reserve


The right to change specifications without notice.

Silent Type (with Soundproof Canopy)

STANDARD GENERATOR DIMENSION AND WEIGHT







Open Type (without Soundproof Canopy)

