

Mikas Middle East FZE

Office No: 139/A, Building -Q1-04 **Sharjah Airport International Freezone** PO Box: 61397, Sharjah **United Arab Emirates.**

Machinery for Industrial Kinetics, Access, and Services

mikas.ae

350 KVA 3 PHASE 50H



GENERATING SET MODEL UPS P 350		
Output Ratings _ 380-415 V, 3 ph, 50 Hz, 1500 rpm	Prime	Standby
	350 KVA	400 KVA
	280 KW	320 KW
380-415 V, 3 ph, 60 Hz, 1800 rpm	400 KVA	438 KVA
	320 KW	350 KW

ENGINE/ TECHNICAL DATA

Ratings at 0.8 Power Factor

Engine Make	PERKINS
Engine Model	2206A-E13TAG2
Governing Type	Electronic
Number of Cylinders	6
Cylinder Arrangement	Vertical in line
Bore and Stroke mm	130 X 157
Displacement/ Cubic Capacity litres	12.5
Induction System	Turbocharged and air to air charge co
Cycle	4 stroke

Frequency and Engine Speed	50Hz & 1500rpm	60Hz & 1800rpm
Compression Ratio	16.3:1	
Combustion System	Direct Inj	ection
Cycle	4 strok	e
mauction system	ruibochargeu an	u all to all charge co

Gross Engine Power kW(hp)	324(434)	468(493)
Fuel Consumption @50% load L/hr @75% load L/hr @100% load L/hr	37 54 71	43 62 81
Total Lubrication System Capacity litres	40	40
Total Coolant Capacity (inc. radiator) litres	51.4	51.4

Exhaust Temperature: °C





400 KVA 60Hz **3 PHASE**

ALTERNATOR DATA		
Make	UPS/ Leroy Somer	
Model լ	UPS314F/LSA (TAL) 46H	
No. of Bearings	1	
Insulation class	Н	
Wires	6/12	
Ingress Protecti	ion IP23	
Excitation Syste	em Shunt	

Overspeed	2250 mn-1
Voltage Regulation (August Voltage Regulation (A	±1%

2/3

CONTROL PANEL

Winding Pitch

Make	DeepSea
Model	7000 Series

The DSE 7000 series is an Auto Start Control Module for single genset applications. It includes doledbacklit LCD display which clearly shows the status of the engine all the times. This module can either be programmed using the front panel or by using the DSE configuration suite PC software. Metering and Alarm Indications:

- Underspeed, Overspeed Generator volts (L-L-L-N)
- Generator current
 - Engine oil pressure
- Engine coolant temperature Hours run counter
 - Battery volts
 - Fail to start/stop
 - Emergency stop
 - Failed to reach loading voltage/frequency
 - Charge fail
 - Low DC Voltage
 - CAN diagnostics and CAN fail/error



STANDARD SPECIFICATIONS

350 KVA 3 PHASE 50H

1. ENGINE

Perkins four stroke heavy duty high performance industrial type 7.1 INSULATION SYSTEM diesel engine.

2. ENGINE FILTRATION SYSTEM

- Cartridge type dry air filter.
- Two cartridge type fuel filter.
- Full flow lube oil filter.
- All filters have replaceable elements.

3. COOLING RADIATOR

Radiator and cooling fan, complete with safety guards designed to cool the engine at high ambient temperatures (consult your dealer for de-ration factors)

4. EXHAUST SYSTEM

Exhaust gas flow 31..3 (m3/min) Maximum allowable back pressure 18.0 (kPa)

5. CIRCUIT BREAKER TYPE

3 pole MCCB. (4 pole is optional)

6. FUEL SYSTEM

The baseframe design is incorporated with an integral fuel tank with a capacity of approx.. 8 hours running at Full load. The tank is supplied complete with fill cap breather, fuel feed and return lines to the Engine and the drain plug.

7. ALTERNATOR

- The insulation system is Class H.
- · All windings are impregnated in either a triple dip thermoset-Ting liquid, oil and acid resisting polyester varnish or vacuum pressure impregnated with a special polyester resin.
- · Heavy coat of antitracking varnish additional protection Against moisture or condensation.

7.2 AUTOMATIC VOLTAGE REGULATOR (AVR)

The fully sealed Automatic Voltage Regulator maintains

The Voltage Regulation at ±1%. Nominal adjustment by means of a trim pot incorporated on the AVR.

8. MOUNTING ARRANGEMENT

8.1 COUPLING The Engine and Alternator are directly coupled by means of an SAE flange. The Engine flywheel is flexibly coupled to the Alternator rotor. 8.2 ANTI-VIBRATION MOUNTING PADS

Agreti-Vibration pads are affixed between Engine/Alternator feet and the Baseframe thus ensuring complete vibration isolation of the rotating assembly. **8.3 SAFETY GUARDS**

The Fan & Fan Drive along with the battery Charging Alternator are Safety Guard protected for personnel protection.

60Hz

400 KVA 3 PHASE

9. FACTORY TEST

- The Generating set is load tested before
- dispatch All protective devise control functions and site load conditions are simulated. The generator and its systems are checked before dispatch

10. EQUIPMENT FINISHING

All mild steel components are fully degreased and painted wit powder coated paint to ensure maximum scuff resistance and

Operation & Maintenance manual, Circuit wiring diagrams and Commissioning/ Fault Finding instruction leaflets are accompanied with the Generator.

12. QUALITY STANDARDS

The equipment meets the following standards, BS4999, BS5000, BS5514 IEC 60034, VDE0530, NEMA MG 1.22 and ISO 8528.

13. WARRANTY


All of the Generating sets are covered under a warranty policy For a period of 12 months or 1000 working hours. Warranty of the equipment is in line with manufacturers warranty terms & conditions. (check warranty statement for more details, as it may vary for different countries.)


In line with the continuous product development, we reserve


The right to change specifications without notice.


Silent Type (with Soundproof Canopy)

STANDARD GENERATOR DIMENSION AND WEIGHT









Open Type (without Soundproof Canopy)

